



MARGARET LESHER THEATRE LIGHTING INVENTORY

1601 Civic Dr. Walnut Creek CA 94596 (925) 295-1400 lesherartscenter.org

<u>INSTRUMENT TYPE</u>	<u>WATTAGE</u>	<u>TOTAL</u>	<u>IN PLOT</u>	<u>SURPLUS</u>
6X9 Strand Leko	1Kw	10	00	10
6X12 Strand Leko	1Kw	30	00	30
6X16 Strand Leko	1Kw	17	02	15
19° ETC Source-4	750w	20	10	10
26° ETC Source-4	750w	36	16	20
36° ETC Source-4	750w	20	00	20
50° ETC Source-4	750w	20	00	20
PAR 64 MFL	1Kw	36	12	24
6" Fresnel Altman	500w	10	00	10
6" Fresnel Strand	1Kw	18	04	14
8" Fresnel Strand	2Kw	12	12	00
L&E MINI-STRIP 6' 3- Circuit	750w / Circuit	04	00	04
FAR CYC 2- Cell Colortran	1Kw / Cell	05	05	00
FLOOR CYC- 3- Cell Colortran	1Kw/ Cell	04	00	04
14" SCOOP	1Kw	05	05	00
19° ETC Source-4 + Seachanger CYMG	750w	08	08	00
26° ETC Source-4 + Seachanger CYMG	750w	08	08	00
LYCIAN SUPER ARC	HTI400w	02	02	00



MARGARET LESHER THEATRE LIGHTING INVENTORY

1601 Civic Dr. Walnut Creek CA 94596 (925) 295-1400 lesherartscenter.org

SUPPLEMENTARY INVENTORY SUPPLIES:

STRAND PATTERN HOLDERS: 15
SOURCE-4 PATTERN HOLDERS (B Size): 15
6" TOPHATS: 12
8" TOPHATS: 12
6" BARN DOORS: 12
8" BARN DOORS: 10

CABLE: STAGE PIN CONNECTOR

(Cable lengths are approximate and may be subject to change.)

35 @ 10'

35 @ 20'

05 @ 50'

05 @ 100'

25 @ TWOFER

TOP CYC FRAME SIZE: 15 ½" WIDE x 15" HIGH (1 cut/sheet)

FLOOR CYC FRAME SIZE: 10 ¼" WIDE x 13 ¾" HIGH (2 cuts/sheet)

- Lighting Console: ETC ION 2048 w/ 2x20 fader wing
- 192 dimmers at 2.4k each
- Designer remote video available at the tech table in the house

*Please get a new lighting inventory each time you design at lesherartscenter.org
Inventory is subject to change without notice.

SUPPLEMENTARY RENTAL INVENTORY:

Please contact the LCA Production Services Coordinator Toni Kilcoyne at 925.295.1400 for additional information, availability, and scheduling requests



LIGHTING NOTES

1601 Civic Drive Walnut Creek CA 94596 (925) 295-1400 lesherartscenter.org

Special Notes to the Lighting Department

Welcome to the Leshar Center for the Arts. This sheet is intended to make your upcoming tech time run as smoothly as possible.

- The Leshar Center for the Arts maintains a permanent house plot, which may not be altered. We invite you to use the house plot as a foundation to build on as it includes many of the basic washes you may use. House plot units must remain in their hung positions as circuited and as focused.
- The lighting console, remote focus unit and follow spots, if used, must be operated by Center staff and the crew used for the hang must consist of Center approved workers. In order to approve someone not already on our list, please contact the Production Services Coordinator Toni Kilcoyne at 925-295-1400.
- The sooner the design gets to us and we are able to check it the better. Your contract requires that all information (plot, instrument schedule, rental requests etc.) be submitted to the Center no later than four weeks prior to your load-in. If your information is received after the four-week deadline, inventory and rental requests cannot be guaranteed and implementation of your design may be affected.
- The grand drape and all doors must be allowed to close without interference from lighting equipment, i.e., instruments, barn doors, cabling. Frequent strikes and restores may be necessary during the run of your show so cable breaks and labels should be used when appropriate. Unless specifically pre-authorized, all cabling methods are subject to the approval of the LCA electrician on site.
- Only stage management and Center operators are permitted in the booth. All other technical staff must have their own ticket to gain access to the house during a performance. If you wish to view any performance from the house (including opening night) you must obtain a ticket from your producer.
- Please- no food or drink onstage or in the house.
- Your producer has been sent a detailed information package concerning every aspect of the Center's operation, including lighting. Additional information about our facilities is available at lesherartscenter.org.